

REPORT- LV-I Details of Constructions

WEATHER FILE- SEATTLE BOEING FI WA

NUMBER OF CONSTRUCTIONS 28      DELAYED 24      QUICK 4

CONSTRUCTION NAME	U-VALUE (BTU/HR-SQFT-F)	SURFACE ABSORPTANCE	SURFACE ROUGHNESS INDEX	SURFACE TYPE	NUMBER OF RESPONSE FACTORS
2015 SEC ALL Deck Roof Const	0.027	0.70	3	DELAYED	4
2015 SEC ALL Mass Wall Const	0.057	0.70	3	DELAYED	9
2015 SEC ALL Stl Fm Wall Const	0.055	0.70	3	DELAYED	6
2015 SEC ALL BG Mass Wall Const	0.070	0.70	3	DELAYED	9
2015 SEC ALL Joist Floor Const	0.029	0.75	3	DELAYED	6
Proposed ALL Deck Roof Const	0.038	0.70	3	DELAYED	4
Proposed ALL Mass Wall Const	0.332	0.70	3	DELAYED	9
Proposed ALL Stl Fm Wall Const	0.118	0.70	3	DELAYED	6
Proposed ALL BG Mass Wall Const	0.267	0.70	3	DELAYED	7
Proposed ALL Joist Floor Const	0.061	0.75	3	DELAYED	6
A90.1-07 NR_R Roof Const	0.048	0.70	3	DELAYED	5
A90.1-07 NR Abv-G Wall Const	0.065	0.70	3	DELAYED	6
A90.1-07 R Abv-G Wall Const	0.065	0.70	3	DELAYED	6
A90.1-07 NR Floor Const	0.038	0.70	3	DELAYED	6
A90.1-07 R Floor Const	0.038	0.70	3	DELAYED	6
A90.1-07 NR Mass Wall Const	0.104	0.70	3	DELAYED	9
A90.1-07 R Mass Wall Const	0.090	0.70	3	DELAYED	9
Interior CMU Wall Const	0.491	0.70	3	DELAYED	6
Interior Frame Wall Const	0.132	0.70	3	DELAYED	4
Interior Ceiling Const	0.514	0.70	3	DELAYED	3
Interior Floor Const	0.813	0.70	3	DELAYED	5
Slab on Grade Const	0.085	0.70	3	DELAYED	40
Below-Grade Wall Const	0.500	0.70	3	QUICK	0
Proposed ALL Slab Wall Const	0.352	0.70	3	DELAYED	7
Resi Core Walls Const	0.283	0.70	3	DELAYED	15
Default Air Wall Construction	2.700	0.70	3	QUICK	0
Below Grade Unins Concrete Wall	0.278	0.70	3	QUICK	0
Exposed Garage Walls	0.740	0.70	3	QUICK	0